Napa Valley College Facilities Master Plan

2016/17

Approved3/9/17

Facilities Master Plan Objectives

Educational Master Plan

In December of 2003 Napa Valley College completed its first comprehensive Facilities Master Plan since the initial construction of the central buildings in the 1960's. The master plan has been subsequently updated in two increments in 2004 and 2009 to reflect the changing campus conditions and needs. In 2014 an update for was begun but not finalized.

The Educational Master Plan highlights specific facilities-related items and provides direction for others. Specifically included are:

- Creation of larger format classrooms
- Constructing additional lab space for the Physical Science programs
- Update and improve technology in classroom space

General direction is indicated for:

- Develop flexible classroom spaces to host a variety of instructional modalities
- Providing permanent space for instruction currently located in portable facilties
- Provide space that will allow for growth of programs and services that support student success and retention

A faculty survey, conducted during the spring semester 2016, found support for larger flexible classroom spaces with an equal number of responses for traditional student desks and moveable tables and chairs. Nearly all responses indicated a need for additional technology i the classrooms as well as the need for small group work that is not possible in many of our current classroom configurations. Half of the responses indicated a need for additional d)-4(p)-4l(a)-10(ce)-4(s)-4(f)-4o(r)-4 s)-24(t)-4o(r)-4a)-24(g)-4e i)-24n t)-4h)-4e c)-4l(a)-4s(s)-4r(o)-4o(m)-4s.o-vemets,i(t)-14(is)-18(c)-6ri(t)-14i ca to-have(a)-1

Preserve the quality and utility th

The tennis courts, constructed in 2006, are in good overall condition but are due for resurfacingin 2017. LED retrofit lightingwas added in 2013 funded by Prop 39.

Baseball field following rain storm (2015)

The campus landscapes are very diverse in design as well as age and maturity. Significant portions of the design and planting material around the central buildings date to the original construct0t0

The Pedestrian Mall links buildings on both levels of the two-tier campus. While building accessibility has been greatly improved in recent years, there remain deficiencies that need to be addressed for ADA accessibility throughout the campus. The Pedestrian Mall forms the major north-south spine to the campus, around which the original campus buildings are organized. The mall, which originally extended from the Gymnasium (Bldg. 300) to the Administration Building (Bldg. 1500), was extended to connect the Performing Arts Center (Bldg. 100) and the LLRC (Bldg. 1700) on either end of the existing mall. There are also east-west components of the mall that extends to the main parking lot at the east, and parking and athletic facilities to the west.

The primary mall section is comprised of concrete and asphalt walkways interspersed with trees in concrete planter boxes. The walkways are lined with pole lights dated back to original construction in 1964. Although retrofitted in 2013 with LED lamps as a Prop 39 project, the poles, lens, and fixtures are past their useful life.

The zelkova trees planted in 1965 in concrete raised planter boxes are at the end of their life expectancy. Root damage over the years has cracked the planters and created uneven walking surfaces in multiple locations.

Pedestrian mall looking south from Gymnasium (2015)

Building 900 and 1100 Infill and Reconfiguration

There is a recognized need for increased space for Student Affairs. Recent changes in funding sources, increased required service levels, and mandated counseling services have all increased needfor dedicated space. Relocation of bookstore to building 200 with student life activities allows for a reconfiguration of the building 900. Added square footage in the Quad area between 1100 and 900 would also allow additional student services space and consolidation of services.

Ag Lab and Viticulture Lab

Site and Utility Upgrades

A series of utility and site projects are required to support the overall campus infrastructure:

- Expand solar panel installation
- Potable Water System: Extension of 4” line along Roy Patrick Drive
- Sanitary Sewer System: Upsizing of sewer systems along Roy Patrick Drive and across fields
    - Replace of pipe in locations impacted by trees.
- Storm Water system: Significant pipe replacement along with catch basis modifications through parking lots and at egress points from campus.
- Hot and Chilled Water Systems (Hydronics): Connection of buildings to be modernized
- Site lighting upgrades; Parking Lots B, G, I and main Pedestrian Mall as well as exterior emergency communication upgrades.
- Parking Lot Upgrades & Potential Expanded Parking: Parking Lot G, south of the Green and west of the McCarthy Library; Parking Lot I, west of Bld. 1200 needs new base and paving, additional planters with trees and drought tolerant landscaping, and new energy efficient lighting

The Outdoor Education Labs project will provide outdoor educational spaces and will include an interpretive trail along the college's restored riparian corridor and pond, both elements of the historic Tulucay Creek. The project will provide outdoor lab spaces for Life Sciences, Environmental Science, Hydrology/ Engineering, and Geology. It is planned that this project will include access to the nearby Napa River, including the floodplain and seasonal wetlands, for expanded educational opportunities.

A new Environmental Education Center located on College property in the Mt. Veeder area could provide lab, classroom and support space for various science and agriculture classes that would take advantage of the natural and agricultural settings the property offers. The lack of physical infrastructure has limited the College's ability to fully utilize the property.

Roof Matrix for Repairs and Replacement Scheduling

Building	Building Description	age	schedule Yr	cost factor	Size	estimate
600	GYMNASIUM, PHYSICAL EDUCATION	26	2017	18.00	12,800	$230,400.00
600	GYMNASIUM, PHYSICAL EDUCATION	26	2017	18.00	16,375	$294,750.00

4090

Scheduled Maintenance Non -Roofing

Plan Year	Project	Age	Estimate
2017	Replace rainwater leaders and storm lines 1100 and 1400	55	$100,000
2018	Replace HVAC in Bldg. 800 (1000A)- 1st and 2nd Floor	36	$125,000
2018	Replace HVAC in Bldg. 800 (1000A)- 3rd Floor	36	$75,000
2018	Replace carpet- Bldg. 600 (1100) gym offices- Lower Floor	22	$33,000
2018	Replace HVAC in Bldg. 1000 (1000B)	36	$200,000
2019	Replace shower partitions and plumbing Bldg. 600 (1100)- Lower Floor	28	$486,000
2019	Replace HVAC in Bldg. 1200 (900)- Lower floor	40	$296,000
2019	Replace HVAC in Bldg. 1200 (900)- Upper floor	40	$296,000
2019	Insulation Abatement in bldg. 1200 (900)	45	$393,000
2020	Renovate and Replace pedestrian walkway and lighting through Campus Center for trip and fall and ADA path of Travel	52	$1,000,000
2020	Upgrade 3 exterior pergolas to meet seismic standards	50	$500,000
2020	Replace elevator (upgrade to ADA) in bldg. 800	36	$480,000
2020	Replace HVAC in Bldg. 1800 (700)- Lower floor	52	$423,000
			$423,000
			$150,000

Facilities Condition Index Primary Buildings

Bldg.Name	Bldg. #	SQFT	YR BLT	Cost per SF	Repair Est	Replace Est	FCI

VWT-AGRICULTURE LAB	3220	1,452	1946	$506.22	$447,041